



Tunnel 70



| Heating Area | |
|------------------------------|--------------------------|
| Tunnel Inlet | 25.5" x 13.75"H |
| Tunnel Length | 47" |
| Shrink Film Types | All |
| Performance | |
| Tunnel Heater Wattage | 14KW |
| Power Supply | 208V / 3ph / 35A |
| Display & Controls | |
| Water Resistant LED Display | ✓ |
| Digital Display | ✓ |
| Customizable Programs | 9 |
| Operational Features | |
| Programmable Conveyor Speed | ✓ |
| Adjustable Air Flow | ✓ |
| Automatic Cool-Down | ✓ |
| Adjustable Conveyor Height | ✓ |
| Self-Rotating Conveyor Rolls | ✓ |
| Double-Insulated Walls | ✓ |
| 18" Exit Roll Conveyor | ✓ |
| Service | |
| Easy Frontal Access | ✓ |
| Indicating Display | ✓ |
| Error Codes | ✓ |
| 1 Year Limited Warranty | ✓ |
| Housing & Dimensions | |
| Material | Steel / Baked Enamel |
| Machine Size (W x L x H) | 71.65" x 47.24" x 64.57" |
| Working Height | 34" |
| Locking Casters | ✓ |
| Weight (Net/Shipping) | 913 lbs / 1065 lbs |
| Optional Features | |
| Teflon Belt | ✓ |

Specifications may change without notice.